

別紙 A - 2 - 4

⑩【H10.09.14】

● 事業を実施しない場合

様式-5

水系名:利根川

河川名:利根川

国勢調査年:H17

事業所統計調査年:H13

流量規模:1/30

氾濫ブロック	一般資産被害額							農作物被害額			公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計	備考	
	家屋	家庭用品	事業所資産		農漁家資産		小計	水稻	畑作物	小計			清掃労働対価	代替活動等	小計						
			償却	在庫	償却	在庫															
A	226,280	147,812	60,503	37,748	1,595	484	474,422	4,513	8,106	12,619	803,672	13,649	5,453	4,403	9,856	8,741	0	8,741	1,322,959		
B	363,069	231,532	100,793	61,868	1,353	411	759,026	2,383	15,878	18,261	1,285,790	23,505	8,683	6,650	15,333	16,703	0	16,703	2,118,618		
C	63,517	92,666	26,741	11,173	286	89	194,472	1,231	11	1,242	329,436	4,512	3,661	3,335	6,996	2,993	0	2,993	539,651		
D-1	63,925	73,349	20,662	7,306	655	232	166,129	7,493	64	7,557	281,421	3,329	2,898	3,199	6,097	2,307	0	2,307	466,840		
D-2	2,080	1,908	724	281	68	25	5,086	45	5	50	8,616	141	76	102	178	84	0	84	14,155		
E	769,218	793,973	364,927	146,798	1,915	669	2,077,500	14,721	7,588	22,309	3,519,284	70,476	32,764	44,688	77,452	32,752	0	32,752	5,799,773	148.5km	
F1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
F2	218,727	336,597	77,363	33,390	265	83	666,425	176	253	429	1,128,923	15,420	13,848	12,226	26,074	12,584	0	12,584	1,849,855		
F3	80,130	55,013	20,112	13,996	255	82	169,588	903	2,197	3,100	287,281	4,388	2,076	1,874	3,950	2,940	0	2,940	471,247		
G	31,556	48,992	7,208	4,125	307	94	92,282	1,104	8	1,112	156,326	1,856	1,930	1,865	3,795	2,093	0	2,093	257,464		
H	37,268	26,379	11,937	5,036	97	18	80,735	165	571	736	136,766	3,406	1,331	2,155	3,486	418	0	418	225,547		
I	11,948	11,203	5,251	2,088	42	8	30,540	55	117	172	51,733	1,214	448	527	975	216	0	216	84,850		
合計	1,867,718	1,819,424	696,221	323,809	6,838	2,195	4,716,205	32,789	34,798	67,587	7,989,248	141,896	73,168	81,024	154,192	81,831	0	81,831	13,150,959	(単位:百万円)	

● 事業を実施した場合

様式-5

水系名:利根川

河川名:利根川

国勢調査年:H17

事業所統計調査年:H13

流量規模:1/30

氾濫ブロック	一般資産被害額							農作物被害額			公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計	備考	
	家屋	家庭用品	事業所資産		農漁家資産		小計	水稻	畑作物	小計			清掃労働対価	代替活動等	小計						
			償却	在庫	償却	在庫															
A	198,021	135,244	56,997	35,225	1,444	445	427,376	4,378	7,867	12,245	723,973	12,677	5,010	4,151	9,161	8,082	0	8,082	1,193,514		
B	334,872	219,878	93,698	57,403	1,286	389	707,526	2,319	14,969	17,288	1,198,547	22,066	8,150	6,194	14,344	16,011	0	16,011	1,975,782		
C	59,114	85,885	26,623	10,636	273	86	182,617	1,200	11	1,211	309,353	4,326	3,451	3,250	6,701	2,812	0	2,812	507,020		
D-1	62,715	72,503	20,315	7,218	644	229	163,624	7,444	64	7,508	277,178	3,269	2,871	3,170	6,041	2,269	0	2,269	459,889		
D-2	1,872	1,450	581	203	56	20	4,182	44	5	49	7,083	118	65	91	156	57	0	57	11,845		
E	637,814	674,319	306,346	123,637	1,707	598	1,744,421	13,778	6,871	20,649	2,955,049	59,004	27,194	37,145	64,339	27,589	0	27,589	4,871,051	148.5km	
F1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
F2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
F3	77,593	53,537	19,645	13,633	243	78	164,729	880	2,049	2,929	279,050	4,288	2,025	1,830	3,855	2,860	0	2,860	457,711		
G	30,634	47,388	6,721	3,928	300	92	89,063	1,101	8	1,109	150,875	1,758	1,834	1,822	3,656	1,970	0	1,970	248,431		
H	14,489	5,703	4,955	2,227	10	1	27,385	113	333	446	46,392	1,933	623	1,125	1,748	63	0	63	77,967		
I	3,828	2,643	2,143	857	2	1	9,474	39	68	107	16,047	680	163	253	416	59	0	59	26,783		
合計	1,420,952	1,298,550	538,024	254,967	5,965	1,939	3,520,397	31,296	32,245	63,541	5,963,547	110,119	51,386	59,031	110,417	61,772	0	61,772	9,829,793	(単位:百万円)	

(国土交通省のハツ場ダム便益計算資料より)